

MINNESOTA AVENUE GULLY

GULLY STABILIZATION



A large actively eroding gully was stabilized with a rock lined channel on North Lindstrom Lake in August of 2016.

This gully runs directly into the lake without any treatment. The watershed includes a road, an agricultural field, woods, and lawns. Water will now travel more slowly through the rock lined channel as water must deflect and travel through the rocks. Erosion control fabric placed beneath the rocks will help protect the soil and prevent new erosion from occurring in the channel.



Partners:

Ken & Deb Haller
Chisago Lakes Township
Chisago Lakes Lake Improvement District
Chisago Soil & Water Conservation District

Pollution Reduction:

Total Suspended Solids: 61 tons/year
Total Phosphorus: 61 lbs./yr
(BWSR Spreadsheet)

Targeted Water:

North Lindstrom Lake

Completion Date:

August 2016

May I Visit?

No – This project is on private property. You can, however, see some of the project from the Minnesota Ave. Please respect private property.

